



TESTING AND MEASURING EQUIPMENT/ALLOWED SUBCONTRACTING
IEC 60669-2-3:2006-08, Edition 3.0
Switches for household and similar fixed electrical installations –
Part 2-3: Particular requirements – Time delay switches (TDS)

R = Required to be at Lab
S = May be subcontracted
W = May be witnessed at MTL
SF = Specialized Facility
3PPS = Three Phase Power Supply required

Clause	Measurement/testing	Testing / measuring equipment / material needed	Subcontracting
In general	-	Testing equipment according to IEC 60669-1:1998 (Third Edition) + A1:1999 + A2:2006 is suitable for the purpose of this part, as applicable, with the addition given below	R
13.101	Measurement of time delay time	Oscilloscope	R
13.102	Safety Isolating	Transformers intended for SELV or/and PELV circuits	R